

Federal Transit Administration Forum

Asset Management Process and Strategy

Frederick E. Smith, P.E.
Acting SVP & Chief Engineer
Capital Program Management




NYCT Capital Planning Basics

- 20-Year Needs analysis produced every five years as a legislative requirement.
- Five Year Capital Plan is based on 20-Year Needs analyses.
- Asset inventories are a key part of producing the 20-Year Needs and validating five year plan submissions.

NYCT Capital Planning Process

20-Year Needs Assessment



Rolling Five-Year Plan Process



20-Year Needs Assessment



20-Year Needs Assessment

- MTA/NYCT's long-range capital investment strategy.
- Guides departments when preparing capital and operating budgets.
- Needs-based process, not strictly constrained by funding availability.
- Coordinated with the five-year capital plan.



Step 1:

Asset Inventory & Condition Assessment

Asset inventory updated by departments

- Typical asset information includes location, age, most recent capital investment, and condition rating.
- Condition of assets updated with input from maintainers, typically an extract of more detailed maintenance data.
- Determination of whether individual assets are in good repair or not.



Step 2: Investment Pace and Strategy

- Investment pace and strategy statement required for each investment group (e.g., signals, station rehabilitation).
- Provides rationale/justification for investments.
- Investment pace and strategy also guided by other agency planning efforts.



Step 3:


20-Year Needs Assessment

Final Product

- Strategy of investments in five year increments:
 - Number of units (total, in SGR).
 - Investment projections, in dollars and units.
 - Updated every five years.



Project Delivery Process



Five Year Capital Plan Process

- Projects are included based on priorities set in 20-Year Needs Assessment.
- Inclusion is based on various factors:
 - Operating need
 - Operating budget impacts
 - Asset condition
 - Coordination efficiency
 - Technological obsolescence
 - Regulatory mandates (ADA)
- Detailed project scopes, budgets, and impacts are defined through a project scoping process, which can begin prior to Five Year Plan.
- Outcome of project scoping process informs decisions to advance design and construction.

Computer Systems

Project Status Reporting system (PSR)

- Home-grown client-server system for:
 - Project budgets/milestones.
 - Descriptive notes.
- Asset records an addition to the system.
 - Records are a snapshot of 20-Year Needs process.
 - Project-to-asset linkages for reporting on capital projects from asset perspective.
- Outputs include:
 - Capital program progress to MTA Board.
 - Public “dashboard” information.
 - Federal biennial “satisfactory continuing control”.
- Continual enhancements with a dedicated staff of application specialists.

Computer Systems (Cont'd)

- 20-Year Needs and program/project development database.
 - Used by planning & budget personnel.
 - Project information for approved five year plan migrates to agency-wide PSR system.
- Maintenance
 - IT, program areas, operations, and sponsor groups involved in data maintenance – along with planning & budget staff.
 - Cyclical based on five year renewal and update cycle.
 - Federal Biennial reporting requirements.

Cooperative Effort

- Various operating departments and groups.
 - Typically, asset information is an extract of other operating/maintenance data.
 - Staying organized is an effort—tracking responses and working with small asset maintainers.

Four examples of Asset Groups

- Each example has different levels of “sophistication”.
- Different levels of detail depending on the maintaining groups and the needs of the capital plan and 20-year needs process.

Example 1: Track and Switches

- 770 miles of track.
2,400 switches (mainline and yard)
- Multi-leveled inspection and assessment hierarchy; weekly, monthly, quadrennial condition assessment.
- Detailed database by track segment:
 - Defects to be fixed by maintenance.
 - Major issues affecting replacement decisions.
 - Expected remaining useful life.
- Track reconstruction priorities weighed by track access opportunities.



Example 2: Traction Power

- 216 substations; 299 circuit breaker houses; 3,400 miles of power cables.
- Spreadsheet tables updated as needed by sponsor from operating information.
- Asset condition determines SGR status.
- With substations, various components rated separately, informing a component-based investment strategy.
 - Enclosure
 - Rectifier(s)
 - High-tension line-up, etc.



Example 3: Subway Cars

- 6,330 cars in fleet
 - A-Division: 2,800 cars (numbered lines)
 - B-Division: 3,530 cars (lettered lines)
- Replacements programmed on 40-year useful life, based on irreparable structural fatigue.
- Detailed investigations influence specific retirement decisions; 42-year-old cars retained while 36-year-old cars with structural deterioration were retired.
- Detailed car-level maintenance records available, but not germane to the fleet-level dynamics that drive the capital programming process.



Example 4: Stations

Assessing the Station Condition



CONDITION ASSESSMENT INSPECTION PROGRAM
For
PASSENGER STATIONS

STATION INSPECTION MANUAL

Revision History

Rev 1 (4/08) – Updated after condition survey of 359 stations for development of database application, added components, new reporting format and miscellaneous items.

March, 2008


Station Inspection Manual

Rev. 1

- First-time condition-based survey of all NYCT station elements.
- Three coordinated consultant teams collected data over 18-month period.
- Over 14,000 components were rated, including: stairs, platforms, mezzanines, windscreens, and canopies.
- Engineering consultants identified structure and architectural repair needs on a visual basis.

Example 4: Stations (Cont'd)

Condition Survey



Component Condition Rating Distribution by Station



| Station/Component | | | Total Units | Rating Distribution | | | | | | | | | |
|---|------|----------|----------------|---|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Line: | MRN: | ELV | | 5 | 4.5 | 4 | 3.5 | 3 | 2.5 | 2 | 1.5 | 1 | UC |
| Ditmars Boulevard | 1 | | | | | | | | | | | | |
| Street Stairs | Q | | 4 | | | 1 | 1 | 2 | | | | | |
| Interior Stairs | | | 2 | | | | 2 | | | | | | |
| Mezzanine Areas: | | | | | | | | | | | | | |
| | | 1 | | | | | | | | | | | |
| Ceilings and Walls | | | 1 | | | | 1 | | | | | | |
| Floors | | | 1 | | | | 1 | | | | | | |
| Columns | | | 1 | | | | | | 1 | | | | |
| Platform Areas: | | | | | | | | | | | | | |
| | | 1 Island | | | | | | | | | | | |
| Ceilings and Walls | | | 0 | | | | | | | | | | |
| Floors | | | 1 | | | | | 1 | | | | | |
| Thru-Spans | | | 1 | | | | | | 1 | | | | |
| Columns | | | 1 | | | | | | | 1 | | | |
| Platform Edges | | | 2 | | 2 | | | | | | | | |
| Windscreen | | | 0 | | | | | | | | | | |
| Canopy | | | 1 | | | | | | 1 | | | | |
| Vents | | | 0 | | | | | | | | | | |
| Other (ramps, overpasses, piers, embankments) | | | 0 | | | | | | | | | | |
| Total Station Components | | | 15 | 0 | 2 | 1 | 5 | 3 | 4 | 0 | 0 | 0 | 0 |
| | | | 73% | Percent Total Station Components Rated 3 or Worse | | | | | | | | | |

| Station/Component | | | Total Units | Rating Distribution | | | | | | | | | |
|---|------|----------|----------------|---|----------|----------|----------|----------|-----------|----------|----------|----------|----------|
| Line: | MRN: | ELV | | 5 | 4.5 | 4 | 3.5 | 3 | 2.5 | 2 | 1.5 | 1 | UC |
| Hoyt Av-Astoria Blvd | 2 | | | | | | | | | | | | |
| Street Stairs | Q | | 4 | | | | | 3 | 1 | | | | |
| Interior Stairs | | | 4 | | | | | | 4 | | | | |
| Mezzanine Areas: | | | | | | | | | | | | | |
| | | 3 | | | | | | | | | | | |
| Ceilings and Walls | | | 3 | | | | 1 | | 1 | 1 | | | |
| Floors | | | 3 | | | | 1 | 2 | | | | | |
| Columns | | | 3 | | | | 2 | 1 | | | | | |
| Platform Areas: | | | | | | | | | | | | | |
| | | 2 Island | | | | | | | | | | | |
| Ceilings and Walls | | | 0 | | | | | | | | | | |
| Floors | | | 2 | | | | | | 2 | | | | |
| Thru-Spans | | | 2 | | | | | | | 2 | | | |
| Columns | | | 2 | | | | | 1 | 1 | | | | |
| Platform Edges | | | 4 | | | | 4 | | | | | | |
| Windscreen | | | 2 | | | | | | 2 | | | | |
| Canopy | | | 2 | | | | | 2 | | | | | |
| Vents | | | 0 | | | | | | | | | | |
| Other (ramps, overpasses, piers, embankments) | | | 0 | | | | | | | | | | |
| Total Station Components | | | 31 | 0 | 0 | 0 | 8 | 9 | 11 | 3 | 0 | 0 | 0 |
| | | | 55% | Percent Total Station Components Rated 3 or Worse | | | | | | | | | |

- Structural and architectural conditions rated on a scale of 1 (best) to 5 (worst).
- Station reports with photos and descriptions of components with repair needs.
- Database for components and subcomponents.
- Database will be updated and expanded.

Example 4: Stations (Cont'd)

Objectives

Cost-effective

- Maintain components that are still in good condition.

Efficient

- Address more stations in shorter period of time.

Flexible

- Address components individually.
- Design guidelines that reflect efficient spending and the individual needs of each station.

Realistic given funding constraints.

New Approach

Process

Condition Survey

Maintain living condition database of station components system-wide



Station Rehabilitations

14 legacy comprehensive rehabilitations

Station Renewals

Address all component needs at 25 stations plus improve aesthetics

Component Campaigns

Repair or replacement of individual components

Example 4: Stations (Cont'd)

New Approach

```
graph TD; A[Condition Survey] --> B[Station Renewals]; A --> C[Component Campaigns];
```

Condition Survey

Station Renewals

Component Campaigns

NYCT's Results

- Successful program formulation and credibility with funding partners built on foundation of good asset management.
- Basic information on the entire capital asset base is very valuable.
 - Leads to fewer surprises in the area of programming / prioritization.
 - Can foresee the size of the problem/scale of the roll-out for any existing or new asset investment.
 - Simple tools like shared spreadsheets can largely meet this need.
- Consistent reporting over time is critical.
 - Changes over time must be explainable by investment, degradation, or obsolescence.
 - Reinvestment/improvement cycles are long, but so is the capital asset decay curve (mostly); a wide swing should be an aberration.





Project Summary

Planning Number: **MW38-6838**PSE Number: **S32738**Status: **In Design**

07/2010

Program: **Signal Systems**Description: **Furnish Sig Equip: Union Tpk & 71 Av /QBL****Unapproved**

General Information

Overview

Budget

Notes & Issues

Assets

Milestone List

| Milestone | Baseline | Annual Plan | Current | Stat |
|------------------------|----------|-------------|------------|------|
| Design Start | 09/2005 | 07/2006 | 07/31/2006 | A |
| Prelim Eng Completion | 12/2006 | 01/2008 | 01/25/2008 | A |
| Final Design Start | 02/2008 | 02/2008 | 02/08/2008 | A |
| Design Completion | 07/2008 | 12/2009 | 12/31/2009 | A |
| Construction Start | 11/2008 | 09/2011 | 01/31/2012 | F |
| Beneficial Use | | 11/2015 | 03/31/2016 | F |
| Substantial Completion | | 12/2015 | 04/30/2016 | F |
| Construction Closeout | | 05/2016 | 09/30/2016 | F |

Current Phase **Design**Phase Complete **95 %**

Current Budget

| | |
|---------------------|----------------------|
| Pre-Design | 0.00 |
| Design | 10,935,269.65 |
| Construction | 0.00 |
| Consultant Closeout | 0.00 |
| Reserve | 0.00 |
| Total Budget | 10,935,269.65 |

Program Officer: **068 - Fred Smith**
Program Mgr: **096 - Nidhish Patel**
Sponsor Leader: **361 - Tracy Bowdwin**
Design Mgr: **058 - Tarik Basu**
Construction Mgr: **053 - Vyomesh Shah**
Resident Eng:

(646) 252-4345
(646) 252-3904
(718) 694-4761
(646) 252-3192
(646) 695-5520

| | |
|-----------------|----------------|
| Base Budget | 6,053,582.25 |
| Adopted Budget | 10,935,269.65 |
| Encumbered Amt | 10,935,269.65 |
| Est Expenditure | 9,260,025.60 |
| Est At Compl | 139,770,222.83 |
| Approved AWOs | 0.00 |

<

<

>

>

Pre-Approve

006178



Project Summary

Planning Number: **MW38-6838**PSE Number: **S32738**Status: **In Design**

07/2010

Program: **Signal Systems**Description: **Furnish Sig Equip: Union Tpk & 71 Av /QBL****Unapproved**

General Information

Overview

Budget

Notes & Issues

Assets

Asset List (6 Assets)

| Asset Category | Asset ID | Seq | Description | Division | Line | Borough |
|----------------|--------------|-----|---------------------------|----------|------|---------|
| Signal | MW7D-1525-SL | | S/O 67 Av - N/E 71 St | IND | QBL | Q |
| Signal | MW7D-1573-SL | | N/E 71 St - N/O 75 Av | IND | QBL | Q |
| Signal | MW7D-1602-SL | | S/O Union Tpk - N/O Union | IND | QBL | Q |
| Signal | MW7D-1630-SL | | S/O VanWyck-N/O Union T | IND | QBL | Q |
| Interlocking | | | Continental Av | IND | QBL | Q |
| Interlocking | | | Union Turnpike | IND | QBL | Q |



Pre-Approve

Add Asset

006178



Asset Detail



| | | | | | |
|--------------|--------------------------------------|----------|--|------------|-----------------------|
| Asset ID | MW7D-1525-SL | Sequence | | Quantity | 3.82 |
| Category | SIGNAL | | | Agency | NYCT |
| Description | S/O 67TH AV - N/E 71ST (CONTINENTAL) | | | Short Desc | S/O 67 Av - N/E 71 St |
| Manufacturer | | | | Model | |
| Type | Air | | | | |

General Information

Condition

Location

Projects

Project Asset List (4 Project Assets)

| Planning Number | PSE Number | Project Description | Design Start | Constr Award | Subst Compl | Project Total Budget | Fu |
|-----------------|------------|---------------------------|--------------|--------------|-------------|----------------------|----|
| MW56-7027 | | CBTC:QnsBlvdW(50St-71Av)1 | 02/2011 | 12/2013 | | 125,000,000.00 | |
| MW38-6838 | S32754 | Instl SigEquip:UnTpk&71Av | | 02/2012 | 02/2016 | 0.00 | |
| MW38-6838 | S32738 | Furn Sig Eqpt:UnTpk-71 Av | 07/2006 | 01/2012 | 04/2016 | 10,935,269.65 | |
| MW38-6838 | | 2 Intrlkng:UnionTpk&71Av | | 01/2012 | | 362,791,900.00 | |



Save

☐ Show Linear Assets

010-155-2